

Litrage béton des planchers poutrelles hourdis

Poutrelles précontraintes

MONTAGE	COUPE	LITRAGE / m ² *
EMX 13+4		~ 67
EMX 16+4		~ 77
EMX 20+4		~ 92
BETON 13+4 (PPB)		~ 53
BETON 16+4 (PPB)		~ 61
BETON 20+4 (PPB)		~ 72
PSE 12+5 (MC)		~ 65
PSE (12+3)+5 (MC)		~ 78
PSE (12+8)+5 (MC)		~ 100



Poutrelles treillis

MONTAGE	COUPE	LITRAGE / m ² *
EBM 13+4		~ 69
EBM 16+4		~ 86
BETON 13+4 (PPB)		~ 57
BETON 16+4 (TRE)		~ 59
BETON 20+4 (TRE)		~ 61
PSE 12+5 (MC)		~ 65
PSE (12+3)+5 (MC)		~ 80
PSE (12+8)+5 (MC)		~ 106
COFFRANT (11+5)		~ 60
COFFRANT (15+5)		~ 69

* HORS chainage, coffrage, foinnement et remplissage accidentel